



17 December 2004 FI 008

Question: NZS 4541

Interpretation: Fixed Fire Protection Group

Clause 403.1.1

Is the pipework between the backflow preventer and alarm valve considered "pipework upstream of the alarm valves" as referred to in clause 403.1.1

Yes.

Reviewed in 2008 and deemed not applicable to NZS 4541:2007 (applies to 2003 edition)